

URM Database *	1995 Bond + 2009 Roofs Seismic Hazard Reduction: Incremental***	2012 Bond Seismic Hazard Reduction: Incremental***	2012 Bond Full Seismic Retrofit and/or Demolition	2017 Bond Roof level strengthening (+ Additional TBD)	2017 Bond Full Seismic Retrofit and/or Demolition
Ainsworth	X	X			
Alameda			X - SRGP		
Beach	X	X			
Benson	X				X
Beverly Cleary/Fernwood	X			X	
Buckman	X	X			
Capitol Hill	X				
Cleveland	X	X			
Creative Science / Clark	X	X			
Creston	X	X			
Franklin	X		X - SRGP		
George					
Grant	X		X - SRGP		
Hayhurst	X	X			X - SRGP
James John		X			
Jefferson	X	X			
Kelly	X				
Kellogg	X				X
Lent	X				
Lewis **		X	X - SRGP		
Markham	X				
Marysville	X				
Mt. Tabor	X				
Richmond	X				
Rieke	X				
Rigler				X	
Roosevelt	X		X		
Rose City Park	X				
Sabin		X			
Smith	X				
Vernon	X				
Wilcox					
Winterhaven	X				

\* City of Portland Bureau of Development Services URM Database includes schools with at least (1) URM identified load bearing wall per BDS definition. See website for more information: [www.portlandoregon.gov/bds/70767](http://www.portlandoregon.gov/bds/70767)

\*\*\* Incremental strengthening includes structural and/or non-structural seismic hazard reduction completed during summer break. Example project scopes include: URM chimney height reduction or bracing, bracing parapets over entries, removing or bracing non-load bearing hollow clay tile walls, strengthening select wall to roof connections, roof replacements with strengthened diaphragm, connections, braced parapets.